

Treebeard Landscape

June 30, 2015

Bid No. 532-40

Tierrasanta MAD
Landscape Proposal

RE: Clairemont Mesa Blvd Wall Repairs

LOCATION: Clairemont Mesa Blvd. Northside between La Cuesta and Deportola

SCOPE OF WORK:

Provide labor, equipment and material to demo out and remove 2 112"x60" leaning sections of block wall. Remove roots, shrubs and old footings. Dig 2 trenches 124"x2' wide, install concrete footing and install approximately 160 6"x16" 80 per wall Adobe Clump Block, to same height with Mortar Cap backfill and cleanup area.

MATERIALS:	
8%	\$842.40
10%	\$67.40
Labor hrs. 110 @ \$16.98	\$84.24
RENTAL:	\$1,867.80
Bobcat excavator with operator	\$680.00
Demo saw/blade	\$180.00
Disposal costs	\$360.00
Total Cost	\$4,081.84

Recommend: Complete in the next 2 months prior to school starting.

*6/30/15
OK to proceed
[Signature]*

APPROVED BY: Robert W. Smith DATE: 6-30-15

This proposal is valid for 45 days. Any alterations to the scope of work will be charged as an extra to the contract price. All accounts 30 days past due are subject to a 1 1/2% monthly service charge.
info@treebeardlandscape.com

- P.O. Box 2777, Spring Valley, California 91979 (619) 697-8302 Fax (619) 697-0820